



# GREEN ROOFERS

## QUOTE

Faversham Town Council

**Date**  
13 Dec 2022

**Expiry**  
12 Jan 2023

**Quote Number**  
QU-5437

**Reference**  
12 Market Place,  
Faversham

**VAT Number**  
205 8504 25

Green Roofers LTD  
Office 9  
Dalton House  
60 Windsor Avenue  
London  
SW19 2RR  
Tel: 0207 754 0365

Description	Quantity	Unit Price	VAT	Amount GBP
Sedum Blanket System; - Drainage Board - Filter Fleece - Extensive Substrate (60mm) - Sedum Blankets - Cobble Border (300mm) - Delivery to Site in 25kg bags	1.00	950.00	20%	950.00
Perimeter Trim 80mm Aluminium Trim; - 2.5lm Length - Connectors - Delivered & Installed	5.00	36.00	20%	180.00
Retention Trim 80mm Aluminium Trim; - 2.5lm Length - Connectors - Delivered & Installed	3.00	36.00	20%	108.00
Protection Fleece	1.00	45.00	20%	45.00
Extra Over - Inspection Chamber - £95 each - Protection Fleece - £1.50 per sq.m. - Maintenance - POA - Irrigation - POA	1.00	0.00		0.00
Install Service; Labour for Green Roof	1.00	850.00	20%	850.00

This price includes additional cost carry the materials to the roof via a client supplied scaffold or similar approved

Description	Quantity	Unit Price	VAT	Amount GBP
NOTE If the materials need to be carried through the house all surfaces must be securely protected by others before we start				
			Subtotal	2,133.00
			TOTAL VAT 20%	426.60
			<b>TOTAL GBP</b>	<b>2,559.60</b>

## Terms

- A. This quotation is subject to and incorporates Green Roofers Limited's Standard Terms & Conditions which are available on the following Link [https://bit.ly/GR\\_TCs](https://bit.ly/GR_TCs) and the conditions below (the "Quotation"). This Quotation is only valid for 90 days from date of issue.
- B. At least 5 working days' notice in writing, by Purchase Order or other acceptance of this Quotation, is required to ensure that all materials are available for a specified on-site date.
- C. A roof area where the pitch exceeds 10 degrees will require cross-battening measures to be supplied and fitted by an independent waterproofing contractor.
- D. This Quotation is based on Green Roofers Limited's operatives having clear and unrestricted access to be able to complete all works within one continuous visit. If multiple installation periods are required, this may affect the Quotation above.
- E. Day work, if installation is not completed within the anticipated time due to restricted access, is charged @ £25 per hour per man, plus 15% on materials and additional costs.
- F. The vegetation layer will require irrigation for a period of 12 weeks after installation. This is dependent upon season and local climatic conditions. Provision of any irrigation by Green Roofers Limited has not been allowed within this Quotation.
- G. Before commencement of works on site, all necessary edge protection and / or scaffolding must be in place on site (this is not provided by Green Roofers Limited) to enable the installation of Green Roofers Limited's works in a safe manner.
- H. A 110V power supply must be available at roof level (if required).
- I. A 1 inch supply of mains water must be available within 25 metres of the roof area, delivering a minimum of 60 litres per minute.
- J. This quotation is based on the Main Contractor lifting the materials to roof level. This quotation has been based on Green Roofers manually distributing the products around the Roof area themselves. Should the method of lifting differ i.e. hoisting/manual handling to Roof level etc then Green Roofers reserve to renegotiate the quotation.
- K. This quote has been based on full rigid deliveries and a 1 hour offload time has been allowed. Unloaded or standing charge will be charged at £65 per hour per vehicle over the 1 hour window.
- L. This Quotation does not include waste removal (i.e. pallets, plastic off cuts, bulk bags). Please request a Quotation from Green Roofers Limited if this service is required.
- M. This Quotation is based on the drawings you have supplied and a final site measure.